

JAN 22 1982

WELL LOG

OPERATOR: Price Resources

WELL NAME: Elberta #1 LOCATION: C SW/4 NW/4 SW/4 15-4S-19W

COUNTY: Phillips STATE: Kansas

WELL COMMENCED: November 20, 1980 WELL COMPLETED: November 26, 1980

ELEVATION: 2074' K.B. TOTAL DEPTH: 3467'

PRODUCTION: Oil RIG NO: #3

CASING - 8 5/8": 200.09' of used 28# cemented with 80 sxs common 2% gel 3% cc
cement circ

4 1/2" ~~XXXXXX~~: 3464.44' of new 10 1/2# cemented with 175 sxs 50-50 poz mix 18% salt 2% gel
Plugdown @ 6:30 P.M.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

			DEVIATION	REMARKS:
FROM	TO	FORMATION	FROM VERTICAL	
0'	195'			
195'	209'	cement		
209'	905'	shale and clay		
905'	1010'	sand		
1010'	1314'	shale and sand		
1314'	1543'	Red Bed and shale		
1543'	1587'	shale and sand		
1587'	1618'	Anhydrite		
1618'	1633'	shale and lime	1633' - 1/2 degree	
1633'	2065'	shale and lime		
2065'	2290'	shales and lime		
2290'	2510'	shale and lime		
2510'	2680'	shale and lime		
2680'	2795'	lime and shale		
2795'	2963'	lime and shale		
2963'	3104'	lime and shale		
3104'	3210'	lime and shale		
3210'	3300'	lime and shale	3300' - 3/4 degree	
3300'	3330'	lime and shale		
3330'	3424'	lime and shale		
3424'	3467'	lime and shales	3467' - 1/2 degree	
3467'	RTD			

DEC - 2 1980
CONSERVATION DIVISION
Wichita, Kansas