


KANSAS GEOLOGICAL SURVEY
 508 East Murdock
 Wichita, Kansas
 DEC 30 1971



SE NW NW
 (316) 267-0613

21-4-19W

B & B DRILLING, INC.
 207 Petroleum Building
 Wichita, Kansas 67202
 720 UNION CENTER

September 27, 1971

DRILLERS LOG

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 28 1971
 CONSERVATION DIVISION
 Wichita, Kansas

OPERATOR: The R. W. Rine Drilling, Co.
 CONTRACTOR: B & B Drilling, Inc.
 COMMENCED: September 16, 1971
 COMPLETED: September 22, 1971
 TOTAL DEPTH: 3600'

20 BOPD
 EL 1999KB

Re: Fischli #1
SE NW NW Section 21-4S-19W
 Phillips County, Kansas

Ran 8 5/8" set @ 229' w/150 sx

0	232	Surface hole
229	1543	Shale & Sand
1543	1576	Anhydrite
1573	2520	Shale
2520	3100	Shale & Lime
3100	3180	Lime & Shale
3180	3335	Lime
3335	3450	Lime
3450	3550	Lime
3550	3600	Lime
3600		Total Depth

DST # 1 3183 - 3255'
 DST # 2 3282 - 3345'

LOG TOPS DEPTH
 HEEB 3167
 TOR 3191
 LKC 3210
 BKC 3428
 TD 3600

Set 4 1/2" @ 3290 w/35 sx Halliburton Lite
 150 sx Common CFR2 -10% salt

We certify the above and foregoing to be true and correct copy of the log on the #1 Fischli, located in Phillips County, Kansas.

Bill Lohar President

Alma O. Neuser Notary Public

Subscribed and sworn to before me this 27th day of September, 1971. My commission expires May 31, 1974