

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


24-4-20W

Company- BURCH EXPLORATION, LTD
Farm- Lynch No. 1

SEC. 24 T. 4 R. 20W
NE NW SW
450' North & 850' West of SW/4

Total Depth. 3503'
Comm. 11-8-64 Comp. 11-16-64
Shot or Treated.
Contractor Co. Tools
Issued. 1-9-65

County Phillips
KANSAS



CASING:

8 5/8" 202' cem. w/IFP sx.

Elevation 2042 KB

Production Dry

Figures Indicate Bottom of Formations.

Shale & sand	1577
Anhydrite	1603
Shale & Red Bed	1642
Shale	1975
Lime & Shale	3332
Lime	3400
Lime & Shale	3502
Lime & Shale	3503
Rotary Total Depth	

TOPS	
Anhydrite	1577
Heebner	3164
Toronto	3190
Lansing	3206
Base Kansas City	3406
Conglomerate	3444

DST #1. 3227-3245. Op 2 hrs.
Rec. 120' muddy wtr w/few oil
specks. IBHP 1081#/30 mins;
IFP 43#; FFP 108#; FBHP 1044#
30 mins.

DST #2. 3250-3265. Op 2 hrs.
Rec. 780' saltwater. IBHP
1066#/30 mins; IFP 21#; FFP
367#; PBHP 1002#/30 mins.

DST #3. 3275-3290. Op 2 hrs
Rec. 130' Muddy wtr. IBHP
1173#/30 mins; IFP 43#; FFP
108#; FBHP 108 #/30 mins.