

26-4-20W

State Geological Survey
WICHITA BRANCH
JUN 8 0 REC'D

CONTRACTOR'S WELL LOG

OPERATOR:	Baird Oil Company
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	McConnell #1
LOCATION:	N/2 S/2 SE/4, Section 26-4S-20W, Phillips County, Kansas
SPUD DATE:	4-29-80
COMPLETION DATE:	5-8-80

0	1490	Sand & Shale
1490	3332	Shale & Lime
	3332	Rotary Total Depth

Spud at 11:45 p.m., 4-29-80. Drilled 258' of 12-1/4" hole. Ran 6 joints of 8-5/8" 20# casing. (Tally 248.22) Set at 254.72'. Cemented with 175 sacks of common, 2% gel, 3% Ca.Cl. Plug was down at 5:30 a.m., 4-30-80. Cement did circ.

T.D.3332'. Set 1st plug at 840' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug 40' solid bridge with 10 sacks, and rathole with 5 sacks. 50/50 posmix, 6% gel. Job complete at 1:45 a.m., 5-8-80.

SAMPLE TOPS:
Anhydrite 1490'
B/Anhydrite 1521'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the McCONNELL #1, N/2 S/2 SE/4, Section 26-4S-20W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec.-Treas.