

10-4-21W


IMPORTANT
Kans. Geo. Survey request
samples on this well.

S. 10 T4 R. 21 ^{NE} W

Loc. NW SW NE

County -Morton-- Norton

640 Acres
N



Elev.: Gr. 2194'

DF _____ KB 2199'

KANSAS DRILLERS LOG
API No. 15 — 137 — 20,094
County Number

Operator
Bell Brothers

Address P. O. Box 581 Robinson, Illinois 62454

Well No. #1 Lease Name Van Loenen, et al

Footage Location 1650 2310
feet from (N) ~~XX~~ line feet from (E) ~~XX~~ line

Principal Contractor Red Tiger Drilling Company Geologist Company

Spud Date June 24, 1974 Total Depth 3770' P.B.T.D.

Date Completed July 1, 1974 Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	20	223	Common	150	2% gel 3% C. C.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval(s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Bell Brothers** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **1** Lease Name **Van Loenen, etal** Dry Hole

S 10 T 4 R 21 ^{EX} W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	240	Heebner	3415
Clay, Shale & Shells	240	1102	Lansing	3458
Sand	1102	1152	Arbuckle	3730
Shale	1152	1288		
Hard Sand	1288	1292		
Shale & Sand	1292	1350		
Sand	1350	1530		
Hard Shale	1530	1570		
Shale & Sand	1570	1875		
Anhydrite	1875	1905		
Shale & Shells	1905	2225		
Shale & Lime	2225	2805		
Lime	2805	3770		
DST #1 - 3492-3552 Tool open 1-1/2 hrs. Rec: 2148' muddy water ICIP - 1261# FCIP - 1279#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Clifford Van Horn
 Clifford Van Horn Signature
 Geologist Title
 July 11, 1974 Date

