

27-4-26 W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - HARRY GORE
Farm - Nauer

No. 1

SEC. 27 T. 4 R. 26W
SW SW SW

Total Depth. 4055

Comm. 7-9-51

Comp. 7-23-51


Shot or Treated.

Contractor. Veeder Supply & Development Co. ✓

Issued. 8-11-51

County. Decatur

KANSAS



CASING:

8 5/8" 306' cem w/160 sxs.

Elevation. 2605 RB

Production. dry

Figures Indicate Bottom of Formations.

surface soil	30
sand, shale	175
clay, rock	225
sand, shale	303
gray shale	330
shale, shells	630
sand, shale	780
shale, shells	1230
sand, shale	1610
shale	1665
shale, shells	1890
sand	1965
shale, sand	2040
shale, red bed	2195
anhydrite	2235
shale, shells	2665
lime, shale	3145
lime, shale	
some iron	3195
lime, shale	3570
lime	3660
lime, shale	3895
conglomerate	4014
lime	4055
Total depth	

Scout tops:

Topeka	3395
Heebner	3595
Toronto	3610
Lansing	3625
Arbuckle	4011

Plugged @ 240' cem w/15 sxs.
Plugged at 40' cem to surface.