

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

25-4-27W


15-039-00568 (DRL, 1/7/2019)

Company- THE TEXAS COMPANY
Farm- M. T. Munson No. 2

SEC. 25 T. 4 R. 27W
SW SW NE

Total Depth. 3595; PB 3175
Comm. 10-20-51 Comp. 12-3-51
Shot or Treated.
Contractor. Anschutz Drlg. Co.
Issued. 1-26-52

County Decatur
KANSAS



CASING:

8 5/8" 362' cem. w/200 sx
5 1/2" 3595' cem. w/175 sx

Elevation. 2490 D.F.
2492 RB Ind.
Production. Pot. 122 / 23% wtr.

Figures Indicate Bottom of Formations.

soil	5
sand	40
shale	220
shale & shells	900
shale	1000
sand rock	1060
shale	1205
shale sdy	1340
fine gray sand	1405
shale & shells	1540
Anhy.	1590
redbed, shale & shells	1808
lime & shale	2020
shale & shells	2380
shale & lime	3240
lime	3295
lime & shale	3355
lime	3383
lime & shale	3429
lime coring	3451
lime & shale	3595
Rotary Total depth	

Tops:

Topeka	3221
Heebner	3348
Toronto	3377
Lansing	3390
Base K. C.	3580

Elevations:

2493 K.B.
2488 G.L.

40.73 BO & 11.83 BW in 8 hrs.