

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

9-4-27W

COMPANY OKMAR OIL

SEC. 9 T. 4 R. 27W
LOC. SW SW NE

FARM Petracek

NO. 2

COUNTY Decatur
KANSAS

TOTAL DEPTH 3765


COMM. 2-5-67

COMP. 2-12-67

SHOT OR TREATED

CONTRACTOR Leben Drlg.

ISSUED 4-8-67



CASING

20	10
15	8 5/8" @ 218' w/175 sx
12	6
13	5

ELEVATION 2660' KB

PRODUCTION POT 69 BOPD &
10% Wtr./LANS-KC 3638-
46

FIGURES INDICATE BOTTOM OF FORMATIONS

0	1775	Shale
1775	2173	Shale, Redbed
2173	2204	Anhydrite
2204	2684	Shale, Shells
2684	2960	Shale, Lime
2960	3100	Lime, Shale with Hard Sand Streaks
3100	3205	Lime, Shale
3205	3365	Shale, Lime
3365	3510	Lime, Shale
3510	3765	Lime
	<u>3765</u>	<u>RTD - Set 5 1/2" Casing</u>

8 5/8" 8 rd. 24# used surface casing Set @ 218' cemented with 175 sacks Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Petracek #2 Well, located SW SW NE of Section 9, Township 4 South, Range 27 West, Decatur County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

TOPS: SCOUT

*Anhydrite	2173
*B/Anhydrite	2204
Burlgame	3302
Howard	3329
Topeka	3346
Oreado	3396
Heebner	3515
Toronto	3546
Lansing	3559