

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


25-4-27W

Company- THE TEXAS COMPANY
Farm- E. B. Jennings No. 4

SEC. 25 T. 4 R. 27W
NE SW SW

Total Depth. 3573
Comm. 2-4-53 Comp. 2-25-53
Spot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 3-14-53

County Decatur
KANSAS



CASING:
10 3/4" 709' cem. w/625 sx
7" 3567' cem. w/200 sx

2558 (and)
Elevation. 2556 DF
Pmp.

Production. 239 BO & 14 BW

Figures Indicate Bottom of Formations.

lime, red bed & shale	340
shale & shells	954
shale, sand & shells	1170
sand	1250
shale & sand	1275
sand, iron	1365
sand	1455
sand & shale	1600
sandy shale red bed, & lime	1692
red bed	1745
sand	1820
red bed & sand	2053
anhydrite	2084
shale & shells	2330
red bed, shale, lime	2510
lime	2614
shale & lime	2794
lime	2923
lime & shale	2987
lime	3092
lime & shale	3152
lime	3573
Total Depth	

Measurement from BH-KB 5.80',
BE-GL 1.40'.

Tops:
Cimarron Dolo. 2054
Cottonwood 2799
Neva 2848
Red Eagle 2908
Foraker 2951
Tarkio 3084
Burlingame 3173
Howard 3222
Topeka 3286
Heebner 3415
Lansing 3456