

25-4-27


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS COMPANY
Farm- H. T. Munson No. 4

SEC. 25 T. 4 R. 27W
SW SE NW

Total Depth. 3494' PB 3409'
Comm. 1-3-54 Comp. 1-13-54
Shot or Treated.
Contractor. Hannum Drilling Company
Issued. 3-20-54

County Decatur
KANSAS



Elevation. 2481 DF

Production. pmp. 40 BO & 15 BW
in 9 hrs.

CASING:

10 3/4" 648' cem w/275 sx
7" 3496' cem w/175 sx

Figures indicate Bottom of Formations.

sand & shale	163
shale, shells & sand	648
sand, shale & Pyrite	1123
shale & shells	1290
shale, shells & sand	1550
Pyrite lime & shale	1625
Dakota sand	1815
sand & shale	2016
shale & lime	2302
shale, shells & red bed	2430
lime	2453
sandy lime, Pyrite & shells	2615
shale, lime & sand	2760
lime	2807
lime & shale	3012
sandy lime	3129
shale & lime	3147
lime	3350
lime & shale	3416
lime	3499

Total Depth.
TD less 5' table to ground level

Tops:

Cimaron Dolomite	1990
Burlingame	3106
Happy Hollow	3124
Howard	3152
Topeka	3218
Heebner	3345
Toronto	3374
Lansing	3387