

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


26-4-27W

Company- PEEL-HARDMAN OIL OPERATORS
Farm- Nellens No. 1

SEC. 26 T. 4 R. 27W
SE NE SE

Total Depth. 3525'
Comm. 8-29-56 Comp. 9-6-56
Shot or Treated.
Contractor. Peel Bros., Inc.
Issued. 10-20-56

County Decatur
KANSAS



Elevation. 2507'

Production. Dry

Figures indicate Bottom of Formations.

surface clay	40
sand	75
sand-shale	263
shale	490
lime	550
shale	900
sand	930
shale-shells	1320
sand	1350
shale-shells	1590
shale	2005
Anhydrite	2045
shale	2060
shale-shells	2480
shale-lime	2795
brkn lime-shale	2905
shale-lime	2982
shale-lime-pyrite	3095
lime-shale	3170
lime	3186
lime-shale	3245
lime	3430
lime-shale	3490
lime	3525
Total Depth	

Perf. w/24 shots fr 3454-3460, acidized
w/1000 gals. Acidized w/2000 gals.

Perf. w/21 shots fr 3180-87, acidized
w/1000 gals.;

Squeezed Perf; Perf. w/25 shots fr
3180-87, acidized w/1500 gals.;

Perf. & acidized w/5000 gals.;

Perf. 3170-74 w/20 shots, no
increase;

Perf. 3150-58 w/20 shots, no in-
crease;

Perf. 3132-34 w/5 shots, no in-
crease.

TOPS: Geological KB
Anhydrite 2005
Howard 3177
Topeka 3239
Heebner 3370
Lansing-Kansas City 3411
RTD 3525
Cable Tool TD 3542

Perf. 3496-3540; Swabbed 64 gals.
in 1 hr w/show oil.