

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


36-4-27W

Company- THE TEXAS COMPANY  
Farm- R. L Skubal No. 2

SEC. 36 T. 4 R. 27W  
SE NE NW

Total Depth. 3603' PB 3519'  
Comm. 12-5-53 Comp. 12-20-53  
Shot or Treated.  
Contractor. Hannum Drilling Company  
Issued. 3-20-54

County Decatur  
KANSAS



Elevation. 2584 DF

Production. pmp. 56 BO & 48 BW  
in 24 hrs.

CASING:

10 3/4" 700' cem w/350 sx  
7" 3601' cem w/175 sx

Figures indicate Bottom of Formations.

|                            |      |
|----------------------------|------|
| sand & shale               | 320  |
| shale                      | 700  |
| shale                      | 1101 |
| shale, shells, & sand      | 1521 |
| shale, shells & Pyrite     | 1790 |
| shale                      | 1889 |
| sand & shale               | 1939 |
| shale, lime & shells       | 2035 |
| shale                      | 2080 |
| lime                       | 2120 |
| shale                      | 2160 |
| shale & red bed            | 2250 |
| shale                      | 2271 |
| shale & shells             | 2335 |
| shale & red bed            | 2400 |
| shale, shells & sandy lime | 2606 |
| lime & shale               | 2700 |
| lime                       | 2735 |
| shale & shells             | 2835 |
| sandy lime & shale         | 2993 |
| sandy lime                 | 3022 |
| shale & shells             | 3203 |
| sandy lime                 | 3318 |
| shale & lime               | 3454 |
| Hebner shale               | 3459 |
| lime                       | 3576 |
| shale & lime               | 3603 |
| Total Depth.               |      |

|                  |      |
|------------------|------|
| Tops:            |      |
| Cimaron Dolomite | 2082 |
| Cottonwood       | 2829 |
| Red Eagle        | 2941 |
| Toronto          | 3116 |
| Howard           | 3257 |
| Topeka           | 3322 |
| Heebner          | 3453 |
| Lansing          | 3495 |