

WICHITA BRANCH

35-4-27W

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

Dupont Oil Company
Abercrombie Drilling, Inc.
Sprester #1
C NE NW NE Section 35-4S-27W
Decatur County, Kansas
June 6, 1978
June 15, 1978

0	355	Surface soil, sand & shale
355	1140	Shale
1140	1755	Shale & sand
1755	1768	Shale
1768	2095	Sand
2095	2125	Anhydrite
2125	2791	Shale
2791	3245	Lime & shale
3245	3250	Lime
3250	3367	Shale & lime
3367	3570	Lime
3570	3590	Lime & shale
3590	3597	Lime
3597	3632	Lime & shale
3632	3674	Lime
	3674	Rotary Total Depth

Spud hole at 4:15 p.m., June 6, 1978. Drilled 355' of 12 $\frac{1}{4}$ " hole. Ran 10 joints 8-5/8" - 28# surface casing. Set at 351' K.B. with 225 sacks of 60/40 posmix, 3% CaCl, 2% gel. Cement did circulate. Job complete at 10:15 p.m., June 6, 1978.

T.D. 3674'. Ran 88 joints of 4 $\frac{1}{2}$ " - 10# casing. Set at 3672' K.B. with 50 sacks of 50/50 posmix, 2% Gel, 12 $\frac{1}{2}$ # gilsonite per sack, followed by 200 sacks common cement, salt saturated. Job complete at 11:15 p.m., June 15, 1978.

SAMPLE TOPS:

Anhydrite 2095' (+ 481)
B/Anhydrite 2125' (+ 451)

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Sprester #1, C NE NW NE Section 35-4S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.