

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

36 - 4 - 27W

COMPANY E. K. EDMISTON & R. W. SHIELDS

SEC. 36 T. 4 R. 27W

FARM Gaumer NO. 1

LOC. NW NE SW

TOTAL DEPTH 3600'

COUNTY

CONM. 10-10-67


COMP. 10-19-67

Decatur
KANSAS

SHOT OR TREATED

CONTRACTOR E. K. Edmiston

ISSUED 3-2-60



CASING

20	10	
15	8	5/8" 240' cen w/ 185 sx
12	6	
13	5	
		4 1/2" 3689' cen w/ 175 sx

ELEVATION 2572' KB

PRODUCTION 53 BOPD PLUS WATER

Task 3157-72

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Clay and Rock	0 - 45
Sand	150
Blue Shale	240
Shale	950
Shale with sandy Lime	1150
Sand and Shale	1585
Shale, sand, lime streaks	1930
Shale	2071
Anhydrite	2109
Shale	2435
Shale and Lime	2660
Lime	2745
Lime and Shale	2880
Lime with Shale Streaks	2995
Lime	3052
Lime and Shale	3210
Lime	3052
Lime and Shale	3210
Shale, Lime and Sand	3264
Lime and Shale	3327
Lime, Shale and Sand	3435
Lime	3585
Lime and Shale	3630
Lime	3690 R.T.D.

The undersigned, E. K. Edmiston & R. W. Shields Drilling Co., Inc., heretofore known as the above log is a true and correct copy of the log in drilling the above well.

TOPS: 100'	
Anhydrite (s)	2071
Base Anhydrite (s)	2109
Cottonwood	2826
Tarkio Lasing;	3167
Howard	3255
Heebner	3450
Toronto	3474
Trailing	3489

E. K. Edmiston of said company, that the above log is a true and correct copy of the log in drilling the above well.

[Signature]