

C O P Y

July 7, 1965

85  
5  
425  
2535  
2205  
428

Burch Drilling Company  
1101 Union Center  
Wichita, Kansas

Re: Joseph Petracek #1  
NW NW NW Sect. 11-4-27W  
Decatur County, Kansas

Gentlemen:

Please use the following instructions in drilling the above described well.

Drilling time: 5' drilling time 2100' to 3200'.  
2' drilling time 3200' to T. D.

Samples (wet): Catch 10' samples 2100' to 3200'.  
Catch 5' samples 3200' to T. D.

Mud: Magabar will handle the mud. Hole to be in shape for possible  
test approx. 3300', 10 c.c. water loss, visc. 40 (will be dis-  
cussed later).

Hole measurement: Strap drill pipe each 1000' and at T. D.

All samples are to be checked for odor and any oil or gas odor recorded under "Remarks"  
on drilling time sheet. Tie samples in even 100' bundles and store in clean dry place.

We are to receive a daily report after you move in. Please be sure that I am notified  
in sufficient time to be on location by 3200'.

Shut down orders - 3350'.

Estimated tops:  
Elevation: 2607'

Anhydrite 2150  
Burlingam lime ~~3275~~ 3318  
Howard 3325 3365  
Lansing 3520  
Arbuckle 3950  
Took 3436

Very truly yours,

NATIONAL ASSOCIATED PETROLEUM COMPANY

David A. Brierley  
WE 2-2998, residence  
LU 2-1181, office

DAB:dc  
Enclosure