

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


4-4-28W

HALLIBURTON OIL PRODUCING CO.
Company- & BURCH DRILLING CO., INC.
Farm- Vavracz No. 1

SEC. 4 T. 4S R. 28W
SE NE

Total Depth. 3950'
Comm. 12-19-59 Comp. 1-4-60
Shot or Treated.
Contractor.
Issued. 3-26-60

County Decatur
KANSAS



CASING:
5 1/2" 3949' w/165 sks.

Elevation. 2686 DE

Production. 140 BOPD

Figures Indicate Bottom of Formations.

shale & shells	1740
shale	2359
anhydrite	2392
shale & shells	2580
lime & shale	3395
lime	3515
lime & shale	3595
lime	3950
Total Depth	

TOPS: SCOUT
Anhydrite 2359

TOPS: ELECTRIC LOG
Heebner 3651
Toronto 3681
Lansing 3699
Base Kansas City 3894

DST #1 3712-3738. Open 1 hour. Recov.
120' muddy oil. IBHP 1230#, IFP 25#,
FFP 50#, FBHP 1150#. (20 min.)

DST # 2 3740-3758. Open 1 hour. Recov.
330' gas, 75' oil, 15' muddy oil. IBHP
1270#, IFP 25#, FFP 40#, FBHP 1250#.
(20 min.)

DST # 3 3763-3815. Open 1 hour. Recov.
465' gas, 255' oil, 120' muddy oil, 60'
very heavy oil cut mud. IBHP 1280#,
IFP 50#, FFP 200#, FBHP 1200#.

DST #4 3817-3845. Open 1 hour. Recov.
4' mud with a trace of oil. IBHP 40#,
IFP, FFP, FBHP 0#.

DST #5 3845-3880. Open 30 min. Recov.
15' mud. IBHP 70#, IFP & FFP 0#, FBHP
20#.