


4-4-28W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- HALLIBURTON OIL PROD. CO. & BURCH DRIG. SEC. 4 T. 4 R. 28W  
Farm- Vavroch No. 2 C NW NE

Total Depth. 3930'  
Comm. 7-18-60 Comp. 7-27-60  
Shot or Treated.  
Contractor. Burch Drig.  
Issued. 11-26-60

County Decatur  
KANSAS



CASING:  
8 5/8" 227' cem w/200 sx.  
5 1/2" 3929' cem w/140 sx.

Elevation. 2732' RB

Production. 90 BOPD

Figures Indicate Bottom of Formations.

shale - shells	780
shale	1430
shale - sand	1875
shale	2002
Anhydrite (Blaine)	2025
shale - shells	2100
shale	2393
C. Anhydrite	2418
shale & lime	2765
lime	2910
lime & shale	3118
lime	3210
lime & shale	3605
lime	3888
lime & shale	3930 RTD
Total Depth	

TOPS:

Blaine Anhydrite	2002
Anhydrite	2393
Topeka	3561
Heebner	3674
Toronto	3704
Lansing	3723

DRILL STEM TESTS:

#1 3650-92', op 1 1/2 hrs., rec. 5' mud & 341' muddy salt wtr. IBHP 1250#, IFP 50#, FFP 160#, FBHP 1150#.

#2 3725-36', op 1 hr., rec. 450' gas in drill pipe, 60' clean gassy oil & 39' muddy oil. IBHP 1240#, IFP 20#, FFP 45#, FBHP 1125#.

#3 3793-3815', op 1 hr., rec. 1290' gas, 424' oil, 30' muddy oil, 60' HO & GCM. IBHP 1155#, IFP 45#, FFP 90#, FBHP 1130#.

#4 3816-38', op 1 hr., rec. 690' oil, 20' muddy oil, 60' VHO & GCM. IBHP 1305#, IFP 70#, FFP 335#, FBHP 1195#.