


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

4-4-28W ✓

Company- HALLIBURTON OIL PROD. & BURGH DR LG. CO. SEC. 4 T. 4 R.28W
Farm- Vavroth No. 8 C NW NW

Total Depth. 3955'
Comm. 9-23-61 Comp. 9-30-61
Shot or Treated.
Contractor. Burch Drlg.
Issued. 2-17-62

County Decatur
KANSAS



CASING:
8 5/8" 250' cem w/220 sx.
4 1/2" 3952' cem w/210 sx.

Elevation. 2734' KB

Production. 29 BOPD

Figures Indicate Bottom of Formations.

shale	1995
shale & sand	2302
shale	2405
Anhydrite	2439
shale & lime	3481
shale-sand-lime	3613
lime & shale	3935
shale	3955 RTD
Total Depth	

TOPS:

Anhydrite	2406
Howard (scout)	3479
Topeka (scout)	3569
Heebner	3681
Toronto	3701
Lansing	3730
Base Kansas City	3921

DST #1 2143-80', op 10 mins, shut in 30 mins. Rec. 300' mud & 900' muddy salt water. IBHP 640#/30 mins. IFP 600#, FFP 640#, FBHP 640#/30 mins.