

4-4-28W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.  
Farm- John Vavroch No. 1

SEC. 4 T. 4 R. 28W  
C NE SE

Total Depth. 4270' PB 4231'  
Comm. 7-1-60 Comp. 9-3-60  
Shot or Treated.  
Contractor. Schafer Drlg. Co.  
Issued. 3-4-61

County Decatur  
KANSAS



CASING:  
8 5/8" 252' cem w/200 sx.  
4 1/2" 4270' cem w/200 sx.

Elevation. 2703' DF

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale 255  
shale 1300  
shale & gypsy 1706  
shale & Anhydrite 2658  
shale & lime 3211  
lime 4020  
lime, shale & sand 4150  
lime 4270  
Total Depth  
Plugged back to 4231'

TOPS:  
Topeka 3558  
Heebner 3671  
Toronto 3701  
Lansing 3718  
Base KansasCity 3910  
Marmaton 3944  
Cherokee 4053  
Conglomerate 4168  
Arbuckle 4245

DST #1 3751-3780', op 1 hr, weak blow  
for 5 mins, rec. 20' drilling mud.  
IFP 30#, FFP 40#, ISIP 995#/30 min.  
FSIP 275#/30 min, IHP 2030#, FHP 2030#.

DST #2 3790'-3823', op 1 hr, weak blow  
for 10 mins & died. Rec. 50' oil & gas  
cut mud. IFP 30#, FFP 40#, ISIP 1115#/30 min.  
FSIP 990#/30 min, IHP 2060#, FHP 2045#.

DST #3 4245-4270', op 1 1/2 hrs, weak blow  
thruout test, rec. 270' muddy water  
IFP 65#, FFP 135#, ISIP - no test -  
slid tool 12' to bottom running test.  
FSIP 890#/30 min, IHP 2280#, FHP 2280#.