

8-4-28W

CONTRACTOR'S WELL LOG

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

GEMINI Corporation
Abercrombie Drilling, Inc.
BISHOP 1-8
NE SW SW Section 8-4S-28W
Decatur County, Kansas
September 20, 1976
September 28, 1976

SEP 30 1985
State Geological Survey
WICHITA BRANCH

0	125	Surface clay
125	170	Sand
170	2571	Shade
2581	2603	Anhydrite
2603	3430	Shade
3430	3788	Shade and Lime
3788	3980	Lime and Shale
3980	4100	Lime
	4100	Rotary Total Depth

Spud at 6:15 p.m. 9-20-76. Drilled 204' of 12 1/4" hole, Ran 5 jts. of 8 5/8" casing (Tally 196'). Set at 203' K.B. with 180 sx. - 60/40 posmix, 3% Ca. Cl. Cement did circulate. Plug was down at 10:15 p.m. 9-20-76

Ran 129 jts. of 4 1/2" new and used casing. (Tally threads off - 4102.38') Set at 4099' K.B. Cemented with 100 sx. 50/50 posmix, 2% gel, 18% Salt, .75% CFR-2. Tailed with 55 sx. Class "A" cement, 1% latex. Plug was down at 4:00 p.m. 9-28-76.

SAMPLES TOPS:

A/Anhydrite 2571'
B/Anhydrite 2603'

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BISHOP 1-8, NE SW SW, Section 8-4S-28W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.
By: Jerry A. Langrehr
Jerry A. Langrehr, Exec. V. P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 1st day of October, 1976.

Sandra Richman
Sandra Richman, Notary Public

