

Company - SINCLAIR PRAIRIE OIL CO.
Farm - Fred Bremer No. 1.

SEC. 28 T. 4 R. 28 W
NWc SE
3 30'fN & W Lines SE $\frac{1}{4}$

Total Depth. 4656'

Comm. 9-2-44


Comp. 9-26-44

Shot or Treated.

Contractor. Holm Drlg.Co.

Issued. 10-28-44

County. Decatur
KANSAS



CASING:

13" 340' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

clay-sand & gravel	135
shale & sand	280
shale sdy	300
shale blue	1070
shale & shells	1310
shale dk-lime shells	1665
lime & shale	1800
shale & lime	1910
shale dk-lime shells	1920
shale sdy	1960
lime & shale	2140
shale red & shells	2185
shale & gyp	2340
shale red	2495
gyp & shale	2545
shale	2560
shale-gyp & lime	2715
lime & shale	2850
shale red	2910
lime sdy hd	2920
shale & gyp	2930
lime gry hd	2955
lime brkn	3040
lime & shale	3100
shale red, lime shells	3200
lime brkn	3220
lime gry hd	3270
lime brwn hd	3285
lime gry hd	3320
lime gry med.	3400
lime gry hd	3600
lime brkn	3621
lime gry med.	3660
lime gry hd	3690
lime	3746
lime-lite hd	3815
lime-lite, med, hd	3929
chert	3930
chert & lime	3945
lime lite hd	3976
lime	3977
lime-lite hd	4031
lime	4057
lime-lite hd	4105
congl	4370
lime & chert	4390
chert	4412

At TD 3976 took drill stem
test as had oil show @
3960-69. Drill stem test
3959-3977 open 45 mins.
recovered 90' salt wtr &
drlg mud, slight show dk
brwn oil
9-30-44 P & A

chert & congl	4424
chert	4426
lime & chert	4500
lime brwn hd	4550
lime gry hd	4560
lime lite med	4656
Total Depth	
Run Schlumberger	