

OPERATOR:	Gemini Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	BISHOP #2-8
LOCATION:	SW SE SW Section 8-4S-28W Decatur County, Kansas
SPUD DATE:	July 2, 1977
COMPLETION DATE:	July 10, 1977

0	208	Surface soil, sand & shale
208	485	Shale
485	2145	Shale & sand
2145	2559	Shale
2559	2593	Anhydrite
2593	2759	Shale
2759	3501	Lime & shale
3501	3596	Shale & lime
3596	3844	Lime & shale
3844	3906	Shale & lime
3906	3965	Lime
3965	3980	Lime & shale
3980	4053	Shale & lime
4053	4100	Lime
	4100	Rotary Total Depth

Spud hole at 5:00 p.m., July 2, 1977. Drilled 208' of 12 $\frac{1}{4}$ " hole, set 193.64' of used 8-5/8", 28#, steel casing set at 202.39'. Cemented with 180 sacks of 60-40 Posmix, no gel, 3% CaCl. Plug was down at 9:00 p.m., July 2, 1977.

T.D. 4100'. Set 1st plug at 1500' with 70 sacks, 2nd plug at 200' with 20 sacks and 3rd plug set at 40' with 10 sacks; Halliburton Cement. Plug was down at 9:30 a.m., July 10, 1977. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:

Anhydrite	2559'
B/Anhydrite	2593'

STATE OF KANSAS	) ss
COUNTY OF SEDGWICK	