

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


7-4-33W

Company- MURFIN-RAINS & WILLIAMSON
Farm- McCain No. 1

SEC. 7 T. 4 R. 33W
C SE SE

Total Depth. 4692'
Comm. 12-8-59 Comp. 12-18-59
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 2-27-60

County Rawlins
KANSAS



CASING:
8 5/8" 302' cem. w/165 sx.

Elevation. 3121 DF

Production. Dry

Figures Indicate Bottom of Formations.

shale	500
shale-sand stks.	1320
shale	1450
shale-sand stks.	1640
shale-w/hard sand	2230
sand-iron stks.	2415
hard sand & pyrite	2520
anhydrite	2585
shale-shells	2750
shale-redbed	2840
anhydrite	2875
shale-lime	4113
lime	4355
lime-shale	4435
lime	4475
lime-shale	4618
lime	4660
conglomerate chert	4668
Mississippi chert	4692
Total Depth	

TOPS: GEOLOGICAL

Anhydrite	2520
Topeka	3854
Heebner	4020
Toronto	4053
Lansing	4062
Base Kansas City	4304
Cherokee	4429
Cherty Conglomerate	4651
Mississippi	4667

DST #1 4075-4113 Open one hour,
rec. 65' mud. IF - 0; FF - 0;
BHP - 130#/20 min.