

15-153-20362
22-4-33W

State
WICHITA BRANCH

CONTRACTOR'S WELL LOG

OPERATOR: Moble C. Hoover
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: George Franklin #1
 LOCATION: C NE NE, Section 22-4S-33W
 Rawlins County, Kansas
 SPUD DATE: January 03, 1980
 COMPLETION DATE: January 13, 1980

0	85	Clay and sand
85	286	Sand and shale
286	2704	Shale and sand
2704	2730	Anhydrite
2730	2824	Shale
2824	3088	Lime and shale
3088	3330	Shale and lime
3330	3535	Shale
3535	3925	Lime and shale
3925	4198	Lime
4198	4330	Lime and shale
4330	4380	Lime
	4380	Rotary Total Depth

Spud hole at 9:30 p.m., January 03, 1980. Drilled 286' of 12 1/4" hole. Ran 7 joints of 8-5/8" new 20# casing. (Talley 278'). Set at 285' R.B. with 200 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 4:00 a.m., January 04, 1980.

T.D. 4380'. Set 1st plug at 1700' with 70 sacks, 2nd plug at 280' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 5 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 8:30 p.m., January 13, 1980.

SAMPLE TOPS:

Anhydrite 2704'
 B/Anhydrite 2730'

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the George Franklin #1, C NE NE, Section 22-4S-33W, Rawlins County, Kansas.