

KANSAS

Kans. Geo. Survey request
samples on this well.


35-4-40W

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 35 T. 4 R. 40 NE

Loc. NE

County Cheyenne

640 Acres
NLocate well correctly
Elev. Cr. 3585'

DF KB 3590'

API No. 15 — 023 — 20150
County Number

Operator

Nielson Enterprises, Inc.

Address

1675 Broadway, Ste. 2770, Denver, CO 80202

Well No.

1

Lease Name

Heaton

Footage Location

1320'

feet from (N) line

1320'

feet from (E) line

Principal Contractor

Western Well Drilling, Inc.

Geologist

W. E. Richardson

Spud Date

9/28/80

Date Completed

11/11/80

Total Depth

1558'

P.B.T.D.

1558'

Directional Deviation

0'

Oil and/or Gas Purchaser

Cheyenne Pipeline

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9-7/8"	7"	17#	327'	Portland	68	None
Production	6-1/4"	4-1/2"	10.5#	1558'	50/50 Poz	125	2% gel, 10% salt, .75% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None					
TUBING RECORD			1 SP2f	3-1/8" SSB II	1334-74' KB
Size	Setting depth	Packer set at			
2-3/8"	1326' KB	None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
56,500 gal 80% foam, 70000# 20/40 sand	1334-74' KB

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
2/18/81	Flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbls.	bbls.	MCF	bbls.	
		89			
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Sold			Niobrara 1334-74' KB		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Nielsen Enterprises, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Gas

Well No.

1

Lease Name

Heaton

S 35 T 4 R 40 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

Niobrara

1335'

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

J. D. Cranor

Signature

Vice President

Title

3/2/21
Date

32-d-1000