

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 31609
Name: Priority Oil & Gas LLC
Address: 633 17th St. Ste 1520
City/State/Zip: Denver, CO 80202
Purchaser: _____
Operator Contact Person: Jessica Trevino
Phone: (303) 296-3435
Contractor: Name: Excell Drilling Company
License: 8273
Wellsite Geologist: none
Designate Type of Completion:
☒ New Well ☐ Re-Entry ☐ Workover
☐ Oil ☐ SWD ☐ SIOW ☐ Temp. Abd.
☒ Gas ☐ ENHR ☐ SIGW
☐ Dry ☐ Other (Core, WSW, Expl., Cathodic, etc)
If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
☐ Deepening ☐ Re-perf. ☐ Conv. to Enhr./SWD
☐ Plug Back ☐ Plug Back Total Depth
☐ Commingled ☐ Docket No. _____
☐ Dual Completion ☐ Docket No. _____
☐ Other (SWD or Enhr.?) ☐ Docket No. _____
1-21-01 1-22-01 2-10-01
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 023-20378-0000
County: Cheyenne
NW-SW-NW Sec. 17 Twp. 4 S. R. 40 ☐ East ☒ West
1655 feet from S / N (circle one) Line of Section
330 feet from E / W (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: McCurry Well #: 2-17
Field Name: Cherry Creek
Producing Formation: Niobrara
Elevation: Ground: 3449 Kelly Bushing: 3455
Total Depth: 1415 Plug Back Total Depth: 1334
Amount of Surface Pipe Set and Cemented at 301 Feet
Multiple Stage Cementing Collar Used? ☐ Yes ☒ No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from n/a
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content 13,200 ppm Fluid volume 3100 bbls
Dewatering method used Evaporate
Location of fluid disposal if hauled offsite:
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ ☐ East ☐ West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Robbie Greis
Title: President Date: May 9, 2001
Subscribed and sworn to before me this 9th day of May,
2001
Notary Public: [Signature]
Date Commission Expires: 3/29/05

KCC Office Use ONLY

☐ Letter of Confidentiality Attached
If Denied, Yes ☐ Date: _____
☐ Wireline Log Received
☐ Geologist Report Received
☐ UIC Distribution

Operator Name: Priority Oil & Gas LLC Lease Name: McCurry Well #: 2-17
 Sec. 17 Twp. 4 S. R. 40 ☐ East ☒ West County: Cheyenne

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☐ Yes ☒ No
 (Attach Additional Sheets)

Samples Sent to Geological Survey ☐ Yes ☒ No

Cores Taken ☐ Yes ☒ No

Electric Log Run ☒ Yes ☐ No
 (Submit Copy)

List All E. Logs Run:

CNL-Density
 Induction-SP-GR
 Cement Bond

☒ Log Formation (Top), Depth and Datum ☐ Sample

Name Top Datum

Niobrara

Beecher Island 1184 2271

CASING RECORD ☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacs Used	Type and Percent Additives
Surface	9 7/8	7"	24#	301	Reg	130	3% cc 1/4# sk flocc
Production	7 7/8	4 1/2"	10.5#	1400	50-50 Pozmix	75	2% gel 10% salt

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
___ Perforate				
___ Protect Casing				
___ Plug Back TD				
___ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
1	1190-1214	500 gal 7.5% HCL	
2	1214-1223	Foam Frac w/ 75,080 #20/40 and 24,480 #12/40	1190-1223
TUBING RECORD Size Set At Packer At		Liner Run ☐ Yes ☐ No	
none			
Date of First, Resumed Production, SWD or Enhr.		Producing Method ☒ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (Explain)	
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls. Gas-Oil Ratio Gravity

Disposition of Gas METHOD OF COMPLETION

Production Interval

☐ Vented ☒ Solid ☐ Used on Lease
 (If vented, Submit ACO-18.)

☐ Open Hole ☒ Perf. ☐ Dually Comp. ☐ Commingled
☐ Other (Specify) _____