

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION**

Form ACO-1
September 1999
Form Must Be Typed

**WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE**

Operator: License # 31609
Name: Priority Oil & Gas LLC
Address: PO Box 27798
City/State/Zip: Denver, CO 80227-0798
Purchaser: Enserco Energy
Operator Contact Person: Jessica Trevino
Phone: (303) 296-3435
Contractor: Name: Excell Drilling
License: 8273
Wellsite Geologist: none
Designate Type of Completion:
☒ New Well ☐ Re-Entry ☐ Workover
☐ Oil ☐ SWD ☐ SLOW ☐ Temp. Abd.
☒ Gas ☐ ENHR ☐ SIGW
☐ Dry ☐ Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
_____ Deepening _____ Re-perf. _____ Conv. to Enhr./SWD
_____ Plug Back _____ Plug Back Total Depth
_____ Commingled _____ Docket No. _____
_____ Dual Completion _____ Docket No. _____
_____ Other (SWD or Enhr.?) _____ Docket No. _____

<u>01/28/03</u>	<u>01/29/03</u>	<u>04/17/03</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 023-20467-00-00
County: Cheyenne
_____ NE _____ SE _____ SW Sec. 30 Twp. 4 S. R. 41 ☐ East ☒ West
1091 feet from (S) / N (circle one) Line of Section
2527 feet from E / (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:

(circle one) NE SE NW (SW)

Lease Name: O'Brien Well #: 6-30

Field Name: Cherry Creek

Producing Formation: Beecher Island/Niobrara

Elevation: Ground: 3509 Kelly Bushing: 3515

Total Depth: 1482 Plug Back Total Depth: 1397

Amount of Surface Pipe Set and Cemented at 218' at ground Feet

Multiple Stage Cementing Collar Used? ☐ Yes ☒ No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from N/A

feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan

(Data must be collected from the Reserve Pit)

Chloride content 18-19,000 ppm Fluid volume 250 bbls

Dewatering method used Evaporate

Location of fluid disposal if hauled offsite:

Operator Name: _____

Lease Name: _____ License No.: _____

Quarter _____ Sec. _____ Twp. _____ S. R. _____

County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Robbie Gris

Title: President Date: 7-2-03

Subscribed and sworn to before me this 2nd day of July

Notary Public: [Signature]

Date Commission Expires: 3/29/05

KCC Office Use ONLY

N Letter of Confidentiality Attached

If Denied, Yes ☐ Date: _____

☒ Wireline Log Received

N Geologist Report Received

_____ UIC Distribution

Operator Name: Priority Oil & Gas LLC Lease Name: O'Brien Well #: 6-30
 Sec. 30 Twp. 4 S. R. 41 ☐ East ☒ West County: Cheyenne

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken ☐ Yes ☒ No
 (Attach Additional Sheets)

Samples Sent to Geological Survey ☐ Yes ☒ No

Cores Taken ☐ Yes ☒ No

Electric Log Run ☒ Yes ☐ No
 (Submit Copy)

List All E. Logs Run:

CNL-Density
 Induction-SP-GR
 Cement Bond

☒ Log Formation (Top), Depth and Datum ☐ Sample

Name Top Datum

Niobrara 1261 2254

Beecher Island

CASING RECORD ☒ New ☐ Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	9 7/8 in	7 in	20 #	224 KB	neat	100	1/4# flo-cele, 3%cc
Production	6 1/4	4 1/2 in	10.5 #	1448 KB	60/40 pozmix	75	6% gypsum, 2%gel

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
☐ Perforate				
☐ Protect Casing				
☐ Plug Back TD				
☐ Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	1262-1303	500 gal 7.5% HCL foam frac	
		w/ 76060 #20/40	1262
		and 25,160 #12/20	1303

TUBING RECORD	Size	Set At	Packer At	Liner Run ☐ Yes ☐ No
none				
Date of First, Resumed Production, SWD or Enhr.	Producing Method ☒ Flowing ☐ Pumping ☐ Gas Lift ☐ Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio Gravity
	N/A	20 MCF/day	0 Bbls/day	

Disposition of Gas METHOD OF COMPLETION Production Interval

☐ Vented ☒ Sold ☐ Used on Lease ☐ Open Hole ☒ Perf. ☐ Dually Comp. ☐ Commingled
 (If vented, Sumit ACO-18.) ☐ Other (Specify)