

CONTRACTOR'S WELL LOG

OPERATOR: Baird Oil Company
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: Hammond #1
LOCATION: C S/2 S/2 SW/4, Section 24-5-18W
Phillips County, Kansas
SPUD DATE: May 17, 1979
COMPLETION DATE: May 20, 1979

0	274	Sand and shale
274	680	Shale
680	1445	Sand and shale
1445	1475	Anhydrite
1475	1963	Sand and shale
1963	2337	Shale and lime
2337	2485	Shale
	2485	Rotary Total Depth

Spud hole at 2:30 p.m., May 17, 1979. Drilled 274' of 12 $\frac{1}{4}$ " hole. Ran 7 joints of 8-5/8" casing. Set at 272' K.B. with 220 sacks of common cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 8:00 p.m., May 17, 1979.

T.D. 2485'. Plugged with 65 sacks of 50/50 posmix, 6% gel. Plug was down at 5:30 p.m., May 20, 1979.

SAMPLE TOPS:

Anhydrite 1445'
B/Anhydrite 1475'

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Hammond #1, C S/2 S/2 SW/4, Section 24-5-18W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.