

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Operator
Rains & Williamson Oil Co., Inc.

Well No. 2 Lease Name
McKinley

Oil

S 24 T 5S R 18W^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 (3110-3190) op30, si30, op60, si30 good blow. Rec 530' MSW FP 83-274#, BHP 1048-990#. Temp 100°				
DST #2 (3190-3240) op30, si30, op60, si40 good blow. Rec 120' Gas in Pipe, 450' Heavy oil, gas & Mud FP 47-216#, BHP 804-757#, Temp 101°				
DST #3 (3235-3230) op30, si30, op45, si30, weak blow. Rec 25' Mud. FP 34-48#, BHP 757-746#. Temp. 101°				
Anhydrite 1363 (+ 599)				
B/Anhydrite 1391 (+ 571)				
Topeka 2872 (- 910)				
Heebner 3070 (-1108)				
Toronto 3096 (-1134)				
Lansing 3114 (-1152)				
B/Kans Cty 3340 (-1378)				
Conglomerate 3416 (-1454)				
Arbuckle 3488 (-1526)				
Granite 3576 (-1614)				
Log Total Depth 3595 (-1633)				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilson Rains
Signature

President-Rains & Williamson Oil Co., Inc.

Title

4-27-76

Date

24-5-18W

COMPANY Rains & Williamson Oil Co., Inc.

SEC. 24 T. 5S R. 18W

FARM McKinley NO. 2

LOC. SE NW SW


RIG. NO. 4

15-147-20,193

TOTAL DEPTH 3597'

COUNTY Phillips
KANSAS

COMM. 8-06-75 COMP. 8-16-75



CONTRACTOR Rains & Williamson Oil Co., Inc.

CASING

20	10	-3/4" @ 210' w/150 sxs common 2% gel, 3% cc.	
15	8		ELEVATION 1962' KB
12	7	7" @ 3492' w/100 sxs common 10% salt	
13	5	3/4 of 1% CFR2.	PRODUCTION Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale & Sand	38
Shale & Shells	890
Sand	1055
Shale & Red Bed	1310
Red Bed & Anhydrite	1359
Anhydrite	1389
Shale	1595
Shale & Lime	2865
Lime & Shale	2950
Lime	3597
<u>Rotary Total Depth</u>	<u>3597</u>



RECEIVED
STATE OF KANSAS

AUG 28 1975

STATE OF KANSAS
GEOLOGICAL SURVEY