

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

508 East Mullock, Wichita, Kansas


10-5-18W

Company - FRANCIS OIL & GAS INC.
 Farm - Parker No. 1

SEC. 10 T. 5 R. 18W
 NE NE NW

Total Depth. 3588
 Comm. 7-19-50 Comp. 7-28-50
 Shot or Treated.
 Contractor. Pickrell Drilling Co., Inc.
 Issued. 8-26-50

County. Phillips
 KANSAS



CASING:

8 5/8" 123' cem w/75 sx.
 Drilled 7 7/8" hole fm 123'-3588' T.D.
 No oil string run.

Elevation. 1979 D.F.
 1981 RB & Q.
 Production. Dry

Figures Indicate Bottom of Formations.

Cellar	5
chalk	75
shale	125
shale, shells	695
sand	1165
shale, shells	1335
sand	1455
anhydrite	1495
shale	1540
lime, shale	2090
shale	2285
lime, shale	2615
shale	2855
lime, shale	3040
lime	3588
Total Depth	

Tops:

Anhydrite	1465
Heebner	3112
Toronto	3135
Lansing	3152
Conglomerate	3494
Arbuckle	3560

(Figures indicate bottom formation-measurements from top rotary bushing.)

Drill Stem Test at 3226-40'.
 Open 30 minutes-recovered 15' mud.

KANSAS Phillips
5 18-W


Sec. 10 Twp. 5 R.

Well No. #1 Parker Farm

Francis Oil & Gas Company

Wildcat Contractor

330 Ft. from N. Line
Ft. from S. Line
330 Ft. from E. Line
Ft. from W. Line



NE NE NW
Seismograph

1950	1979-1981 RB REPORT
7/19	Carter farmout Amerad DHM Stanolind DHM & acreage 8 5/8" @ 122 drlg. 1335

KANSAS Phillips


Sec. 10 Twp. 5 R. 18-W ✓

Well No. #1 Parker Farm

Francis Oil & Gas Company

Wildcat Contractor

330 Ft. from N. Line
Ft. from S. Line
330 Ft. from E. Line
Ft. from W. Line



NE NE NW
Seismograph

Carter farmout Amerad DHM Stanolind DHM & acreage	
1950	Elev 1979
8/2	8 5/8" @ 122 Anhy 11435 Topeka 2901 Heeb 3113 Lans 3137 SO 3240-42 3234-40 good odor fair porosity some free oil DST 3226-40 opn 1 hr rec 15' mud Cong 3490 Arb 3561 TD 3588 D&A FIRST REPORT ABANDONED

Kansas

Map No. _____ Sec. 10 Twp. 5 R. 18W

Well No. 1 Parker

Francis Oil & Gas

Company

MCPC S/2 NE N/2 SE

Contractor

NE NE NW

Sec. 9

SECTION PLAT

330 Ft. from N. Line

Ft. from S. Line

330 Ft. from E. Line

Ft. from W. Line



Phillips County

Siesmograph

Location

Rig up

Drilling and Remarks:

Carter farmout

Amerada BHM

Stanolind DHM & acreage

8 5/8" @ 122

drlg. 1335

RECORD

Cased _____ in. _____ ft.

Sand

Gas

Oil

Total Depth

PRODUCTION

1st 24 hrs. Nat.

1st 24 hrs. after shot

Gas _____ Cu. Ft.

Dry Hole

Abandoned

Date

JUL 19 1950

19

J. E. TYRA

Scout


County Phillips State Kansas

Sec. 10 (Blk. Twp.) 5 (Sur. Rge.) 18W Map No.

Operator Francis Oil & Gas

Well No. 1 Farm Parker

Elev. 1979 Location NE NE NW



330 Ft. From N Line NW

330 Ft. From E Line Quarter

1st. Report

Completion AUG 2 1950

Remarks Seismograph

Carter farmout Amerada

BHM Stanol. DHM & acreage

Spudding Date

Drlg. Data

Wildcat

8 5/8" @ 122 Anhy 1435 Topeka 2901

Heeb. 3113 Lans. 3137 SO 3240-42

3234-40 good odor fair porosity some
free oil DST 3226-40 open 1 hr.

Rec. 15' mud Cong. 3490 Arb. 3561

TD 3588 D & A

J. E. TYRA