

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


3-9-200

Company - STANOLIND OIL & GAS CO.  
Farm B.W. Wiltout "B" No. 1

SEC. 3 T. 5 R. 20 W  
SE NW NE  
4290' NSL 3630' EWL

Total Depth. 3437' PB 3135'  
Comm. 1-18-46 Comp. 2-10-46  
Shot or Treated.  
Contractor.  
issued. 3-23-46

County. Phillips  
KANSAS



CASING:  
13 3/8" 159' Cem.  
5 1/2" 3322' Cem.

Elevation. 1961

Production. Dry

Figures Indicate Bottom of Formations.

cellar	0-10
surface clay &	
sand	65
shale & shells	161
shale	669
shale & shells	1030
sand	1220
shale & shells	1360
sand & shale	1480
lime- anhydrite	1520
shale & shells	1850
shale	1930
shale & shells	2215
shale & sand	2336
lime & shale	
strks	2445
lime & shale	2750
lime	2795
lime & shale	2910
shale & lime	3081
lime	3300
sand	3321
lime	3380
reworked Arb.	3403
Arbuckle	3437
Total Depth. PB 3135'	

Schlumberger Elec. Log to  
Total Depth.  
TD by Schlumberger 3435'  
" " Rotary Drill Pipe 3437'

Tops:  
Lansing 3081  
Reworked Arb. 3380  
Arbuckle 3403

Temperature Survey  
Top of Cem. outside  
of casing 2700'

Perforated Csg.:  
w/12 shots 3170-76'  
w/23 shots 3170-30'  
w/24 shots 3131-36'  
w/12 shots 3130-34'

From completion card:  
23 sh. 3147-53  
(KGS)

Acidized:  
Section 3130-34' w/200 gals.  
acid.

Swab test:  
11 BO & 333 BW in 24 hrs.

Dumped 3 sacks cem. as  
temporary plug.  
Plugged back depth 3178'  
Plugged back total depth 3135'