

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
 508 E. Murdock Wichita, Kansas


14-5-Jow

Company. CITIES SERVICE OIL  
 Farm. RUNDLE No. 1

SEC. 14 T. 5 R. 20W  
 SW NE NE  
 990' S & 990' W of NE Cor.

Total Depth. 3465; PB 3432  
 Comm. 7-3-50 Comp. 7-11-50  
 Shot or Treated. 4500 acid  
 Contractor. R. W. Rine D. lg.  
 Issued. 9-30-50

County. Phillips  
 KANSAS



Elevation. 2106

Production. 11 Oil & 26 wtr/24 hrs.

CASING:

8 5/8" 205' com. w/250 sx  
 5 1/2" 3465' com. w/125 sx

Figures Indicate Bottom of Formations.

surface soil, clay & sand 110  
 sand & shalo 205  
 shalo, sand & shells 900  
 sand 1335  
 shalo & shells 1610  
 Anhydrite 1645  
 shalo & shells 2395  
 lime & shalo 3209  
 lime 3465

RTD 3465 - 3465 SIM

Total depth  
 PB 3432

Tops:

Heebner 3205  
 Dodge 3229  
 Lansing 3246  
 Base Kansas City 3456

Remarks:

Drill stem test 3249-62,  
 rec. 5' oil cut mud and 15'  
 oil in 30 minutes.  
 Drilled cement to 3432 SIM  
 Perf. 71 shots 3246-60  
 Bailed 4-2/3 gals. oil per hr.  
 for 13 hrs.  
 7-19-50 : Acidized 1500 gals.  
 P. 15 oil, 10 wtr/24 hrs.  
 7-22-50; Acidized 3000 gals.  
 Pumped 32 oil, 17 wtr/24 hrs.  
 7 7/8" rotary hole