


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

14-5-20w

Company - CITIES SERVICE OIL CO.
Farm - Templeton No. 5

SEC. 14 T. 5 R. 20 W
NEc SW
330' S & 330' W of Center

County. Phillips
KANSAS



Total Depth. 3504=3503 SLM PB 3331'
Comm. 10-29-46 Comp. 11-7-46
Shot or Treated. Acidized
Contractor. A. W. Fine Drlg. Co.
Issued. 2-22-47

CASING:

8 5/8" 199' Cem. w/200 sx.
5 1/2" 3501' Cem. w/150 sx.

Elevation. 2128 ft

Production. Phy. Pot. 32 BO, 38%
water, 24 hrs.

Figures Indicate Bottom of Formations.

surface clay 0-50
shale & sand 199
shale 240
shale & sand 1340
shale & shells 1630
lime & anhydrite 1665
shale & shells 2085
shale & lime 2664
lime 2785
shale & shells 2915
shale & lime 3330
lime 3430
lime & shale 3500
cored lime (rec.
3') 3504
3504 RTD=3503' SLM
Total Depth PB 3331'

Schlumberger

Tops: (Corr.)

Lansing 3231
Arbuckle 3494
Penetration 9'

Perf. Pen. Lansing 94'
Drilled Cement to 3470' SLM
Perf. 12 shots 3296-3307'
Perf. 36 shots 3299-3311'

11-15-46 Acidized w/2500 gals.
Impd 89 Oil, 49% wtr., 24 hrs.

Set retainer & squeezed 3296-3311'
w/370 sx. 320 sx through perfs.
@ 2600# press.

Drilled cement 3469 SLM
Perf. 47 shots 3297-3309'
11-26-46 Acidized w/2000 gals.
Impd 180 B. fluid, 80% wtr.

Set retainer @ 3270' & squeezed
w/315 sx. cement, 305 sx. through
perfs, 3297-3309' @ 2500# press.

Drilled cement 3428' SLM
Perf. 20 shots 3338-45'
Show salt wtr.
Perf. 24 shots 3319-25'. Small
show oil.
P. B. to 3331' w/rock & cement.

12-17-46 Acidized w/1000 gals. 3319-25'