


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

14-5-20w

Company - CITIES SERVICE OIL CO.
Farm Templeton No. 6

SEC. 14 T. 5 R. 20W
SE SW SW
330' N & 990' E of SW Cor.

County. Phillips
KANSAS



Total Depth. 3579'

Comm. 1-30-48

Comp. 2-15-48

Shot or Treated. See Below

Contractor. R. W. Rine Drlg. Co.

Issued. 5-8-48

CASING:

8-5/8" 155' Cem. W/200 Sx.

5-1/2" 3541' Cem. W/150 Sx.

Elevation. 2139.2nd.

Production. Phy. Pot. 43 BO, 3
BW 24 hrs.

Figures Indicate Bottom of Formations.

clay, shale & shells	155
shale, shells & sand	545
shale & sand	1310
sand & shale	1640
shale & shells	1890
lime & shale	2120
lime brkn & shale	2310
lime & shale	2625
shale & lime	3235
lime	3516
cored lime & shale	
(rec. 4 1/2')	3521
lime & shale	3543
cored lime (red. 4 1/2')	3548 RTD
3548 RTD = 3547 SLM	
lime & shale	3574
lime	3579
Total Depth.	

Tops:

Lansing	3249
Corr. Arbuckle	3511
Penetration	68

2/3 BOPH, trace water

2-17-48 Ax. 500 Gals. Pumped
9 oil, 3 wtr, 11 hrs P.O.

Perf. 16 shots 3536-40
" 22 shots 3510-16

2-21-48 Ax. 500 gals. 3510-16

2-25-48 Pumped 32 BO, 2 1/2 BW 24 hrs.

Acidized W/500 gals. 3541-79 (2-17-48)
Acidized W/500 gals. 3510-16 (2-21-48)