


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas

14-5-204

Company- CITIES SERVICE OIL CO.
Farm- Templeton No. 9

SEC. 14 T. 5 R. 20W
NE NW SW
330' south & 990 east of
W/4 cor.
County Phillips
KANSAS

Total Depth. 3496
Comm. 12-17-53 Comp. 1-6-54
Shot or Treated. 1000 gals.
Contractor. Glenn R. Nye Drlg.
Issued. 1-30-54



CASING:

8 5/8" 190 cem. w/250 sx.
5 1/2" 3488 cem. w/150 sx.

Elevation. 2102

Production. 265 oil,
5 acid water

Figures indicate Bottom of Formations.

soil & clay	40
sand & shale	160
shale	780
shale & sand	870
sand & shale strks	1340
shale & red bed	1600
anhyd.	1635
shale & shells	2000
lime & shale	3235
lime	3489
cored lime	3497
3497 RTD = 3495 SIM	
lime	3496
Total Depth	

Tops: Corr.
Heebner 3175
Dodge 3200
Lansing 3217
Gorham 3477
Arbuckle 3485

Pen. 11'

Fillup: 109' oil in 1 1/2 hrs.
172' oil in 2 3/4 hrs. at 3495 ?
248' oil in 3 hrs. 55 mins at 3496
420' oil in 5 hr. 55 mins.
665 oil in 9 hrs.
1260' oil in 16 hrs.