

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
505 East Murdock, Wichita, Kansas


14-5-20w

Company- CITIES SERVICE OIL CO.
Farm- Templeton No. 11

SEC. 14 T. 5 R. 20W
SW SW SW
1650' N & 330' E of SW Cor.

Total Depth. 3507'
Comm. 11-5-58 Comp. 11-24-58
Shot or Treated.
Contractor. Braden Drlg. Co.
Issued. 1-17-59

County Phillips
KANSAS



CASING:

8 5/8" 240' cem w/250 sx.
5 1/2" 3489' cem w/150 sx.
DV tool @ 1612' cem w/400 sx

Elevation. 2099' Gr.

Production. 81 BO & 5 BWPD

Figures Indicate Bottom of Formations.

sand	40
sand, shale & shells	240
shale & shells	1600
anhydrite	1630
shale & shells	1910
lime	2050
lime & shale	2370
lime	2768
lime & shale	2900
lime	3078
shale	3105
lime & shale	3175
lime	3450
lime & shale	3488
lime	3491
3491 Rotary T.D. =	3490 SLM
lime	3506½
lime	3507
Total Depth	

TOPS: CORR.

Heebner	3181
Dodge	3205
Lansing	3222
Base Kansas City	3427
Arbuckle	3487
Pen.	19½'