

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-5-20w

Company- CITIES SERVICE OIL CO.
Farm- Hansen "F" No. 1

SEC. 15 T. 5 R. 20W
NW NE SE
330' S & 990' W of E $\frac{1}{4}$ cor.

Total Depth. 3537
Comm. 4-26-53 Comp. 5-8-53
Shot or Treated. Acid 500 gals.
Contractor. R. W. Rine Drilling Co.
Issued. 5-30-53

County Phillips
KANSAS



CASING:

8 5/8" 200' cem w/200 sx
5 1/2" 3530' cem w/150 sx

Elevation. 2122

Production. 87 oil . 38 wtr

Figures indicate Bottom of Formations.

sand, shale	0 - 200
shale	940
sand, shale	1400
shale, s shells	1640
anhydrite	1670
shale, shells	2230
lime (sdy), shale	2500
lime	2600
shale, lime shells	2775
lime, shale	2900
lime, shells	3020
shale, lime	3114
lime	3278
lime, shale	3372
lime	3470
shale sdy, lime	3503
lime, shaly sand	3525
Core: lime, shale & sand	3530
lime	3534
RTD 3534 = 3531 SLM	
lime	3537
Total Depth	

Tops: Corr.	
Heebner	3223
Dodge	3245
Lansing	3266
Gorham Sand	3518
Arbuckle	3527
Penetration	10'

Good showoil @ 3534

91 gals oil in 1 $\frac{1}{2}$ hrs. @ 3537

332' oil & 130' wtr in 12 hrs.

7 7/8" rotary hole.