

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg., Wichita, Kansas


21-5-20W

D. G. HANSEN  
Hansen Fee No. 1.

SEC. 21 T. 5 R. 20 W  
CSE SE  
554' f E & S Lines SE $\frac{1}{4}$

Total Depth. 3591'  
Comm. 7-8-43 Comp. 8-19-43  
Shot or Treated.  
Contractor.  
Issued. 10-9-43

County. Phillips



CASING:

10 $\frac{3}{4}$ " 159'  
5 $\frac{1}{2}$ " 3585 $\frac{1}{2}$ '

Elevation.

Production. Pot. 153 B.

Figures Indicate Bottom of Formations.

clay	0-30
shale	50
sand	80
clay	162
shale	950
sand	1155
shale	1355
shale & shells	1675
anhydrite	1713
shale & shells	1830
red bed	1940
shale & lime	1995
shale & shells	2635
lime brkn	2720
lime	2750
shale & shells	2800
shale & lime shells	2870
shale	2920
shale & lime	3045
lime	3120
lime & shale	3204
lime	3523
sdv shale	3535
lime	3583
core	3588
Cored 3583-88 rec. 4 $\frac{1}{2}$ '	
2' green shale	
2 $\frac{1}{2}$ ' sdv lime	
total rotary depth	
Cable Tools -	
lime	3591
Total Depth.	

Perf. w/ 24 shots 3551-59  
Acidized w/500 Gals.  
500 Gals.  
1000 Gals.

Tops: K. C. 3272  
Arbuckle 3569