


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Wichita, Kansas

Company SKELLY OIL COMPANY
Farm B. O. GRAHAM No. 11

SEC. 22 T. 5 R. 20W
SW NE NE
990' fr NL & 990' fr EL NE $\frac{1}{2}$

Total Depth. 3518' 3478 $\frac{1}{2}$ P.B. S.L.M.
Comm. 11-17-48 Comp. 11-28-48
Shot or Treated. acid
Contractor. Claude Wentworth
Issued. 4-2-49

County. Phillips
KANSAS



CASING:

8 5/8" 295' 292' 31" LI com w/ 150 sx
5 1/2" 3512' 553' 6" LI com w/ 200 sx

Elevation. _____

Production. POB 8 hr 29 BO
54 BW Pot of 87 bbl

Figures indicate Bottom of Formations.

surface soil & sand	70
sand	100
sand & shells	295
shale	385
shale & shells	740
sand	800
shale, shells, & sand	1048
sand	1078
shale	1550
red bed	1635
anhydrite	1658
shale	1840
shale, shells	2400
shale, lime	2555
shale	2625
lime & shale	3159
lime	3177
light buff oolitic	
lime	3182
lime	3234
lime oolitic	3236
lime	3238
lime oolitic	3240
lime	3260
lime oolitic	3272
lime	3292
oolitic lime	3298
lime & shale	3350
Porous lime	3352
lime, shale	3429
fine to crys. lime	3431
lime PB 3478 $\frac{1}{2}$	3511
fine crys. granular	
& slightly sdy dolomite	3518
Total depth	

TOPS:

Heobner Shale 3211
Lansing Lime 3234

Producing formation
Lansing Lime 3258' 3352'

3177-3182 Spotted por. & sat.
3234-3236 Fair por. & sat.
3238-3240 Fair por. & sat.
3260-3272 Spotted por. & sat.
3292-3298 Fair por. & sat.
3350-3352 Fair sat.
3429-3431 Por. w/fair sat.
3511-3518 Fair porosity & sat.

12-28-48 700 gal. 3350-3352
12-28-48 700 gal 3292-3298
1-7-49 750 gal 3258-3272