

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


22-5-20W

Company - CITIES SERVICE OIL CO.
Farm - Reese "F" No. 1.

SEC. 22 T. 5 R. 20 W
NE 1/4 SE
330'S 330'W E 1/4 Cor.

Total Depth. 3572'
Comm. 6-2-44 Comp. 6-28-44
Shot or Treated. None
Contractor. R. W. Rine Drlg. Co.
Issued. 8-5-44

County. Phillips
KANSAS



CASING:

8 5/8" 165' Cem.

5 1/2" 3529' Cem.

62'9" of 4 1/2" liner, btm 6' slotted, Set @ 3572'
Figures indicate Bottom of Formations.

Elevation. 2150 E-log.

Production. Phy. Pot. 245 B.
No wtr

surface clay & sand	55
sand	63
clay	165
shale	325
shale & sand	1230
sand & shale	1593
shale	1635
anhydrite	1680
shale	1805
shale & shells	2823
shale & lime	2945
lime & shale	3193
lime	3326
lime cherty	3381
lime	3533

3533 Rot. TD=3531 SLM

dolomite & congl 3537

dolomite 3572

Total Depth.

Tops:

Corr. Eros. Arbuckle 3528

Corr. Arbuckle 3537

Penetration 35

Fillup:

600' oil in 2 hrs.

975' oil in 3 hrs.

1825' oil in 9 hrs.

2150' oil in 13 hrs.