


WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SKELLY OIL CO.
Farm - B. O. Graham No. 7

SEC. 23 T. 5 R. 20 W
SE SW NW
330' fEL & 330' fSL NW $\frac{1}{4}$

Total Depth. 3347'
Comm. 4-15-47 Comp. 5-3-47
Shot or Treated. Acidized
Contractor. Claude Wentworth Co.
Issued. 8-23-47

County. Phillips
KANSAS



CASING:

8 5/8" 255' Cem. w/150 sx.
5 1/2" 3330' Cem. w/150 sx.

Elevation. _____

Production. Pot. 956 Bo.

Figures Indicate Bottom of Formations.

surface soil & clay	0-100	5-5-47 - Acidized w/3000 gals. 3347-3340'
clay & shale	850	5-9-47 - Acidized w/1000 gals. 3260-3281'
sand	880	5-10-47 - Acidized w/3000 gals. 3256-80'.
shale & clay	1050	
shale, shells & clay	1385	
anhydrite	1440	
red bed	1630	
lime	1745	
shale & red bed	1800	
shale & shells	1955	
lime & shale	2070	
shale & shells	2225	
lime & sdy shale	2260	
lime & shale	2375	
lime, shale & shells	2525	
shale & lime shells	2550	
lime & shale	3165	
lime & chert	3200	
lime & shale	3238	
lime gy xlyn	3280	
lime sft brwn oolitic & xlyn, por. & sat.	3281	
lime gy xlyn & shale drk	3309	
lime gy & brwn oolitic & xlyn, por. & med. sat.	3315	
SLM 3315 R.T. = 3310'		
SLM DF.		
(hole filled 600' w/oil in 1 hr., 1000' in 3 hrs., 1300' in 12 hrs., no wtr.)		
chert gy & pink w/trace of lime, no sat.	3318	
lime gy xlyn	3323	
lime gy & brwn xlyn w/25% shale, sli. oil sat.	3330	
lime gy & brwn xlyn & oolitic w/30% shale, sli. sat., poor por.	3335	
lime gy, no por. or sat.	3347	
Total Depth.		

Tops:

Heehner shale 3212
Lansing Lime 3233 SLM