


27-5-20W

CITIES SERVICE OIL CO.  
Pearson "B" No. 1.

SEC. 27 T. 5 R. 20 W  
SW NW SW  
990'S 330'E W  $\frac{1}{4}$  Cor.

Total Depth. 3640'  
Comm. 1-7-43 Comp. 1-18-43  
Shot or Treated. None  
Contractor. R.W. Rine Drlg. Co.  
Issued. 3-13-43

County. Phillips



CASING:  
10  $\frac{3}{4}$ " 151' Cem.  
7" 3640' Cem.

Elevation.

Production. Depth. Pot.  
3000 Oil, NoWtr  
(Ind. Cap. 5626 B.)

Figures Indicate Bottom of Formations

surface sand & shale	0-151
shale & sand	650
shale, shells, sand	1290
red bed & shale	1650
anhydrite	1965
shale	2510
shale & lime	2603
shale	2792
shale & shells	2870
shale	3130
shale & lime	3202
lime	3640
Total Depth.	

Ran Schlumberger

Corr. Top Reagan 3571  
Top Granite Wash 3598  
Top Granite 3636  
Penetration 4

1-25-43 Perf. by Lane-Wells:  
12 shots 3570-74, top sand 3571  
1750' oil in 20 min.  
2425' oil in 50 min.  
2800' oil in 2 hrs  
2850' oil in 3 hrs

Perf. penetration Reagan Sand, 3'