


28-5-202

CITIES SERVICE OIL CO.
Reese "E" No. 1.

SEC. 28 T. 5 R. 20 W
SW¹/₄ SE
330' N 330' E S¹/₄ Cor.

Total Depth. 3692¹/₂'
Comm. 10-14-42 Comp. 10-27-42
Shot or Treated. None
Contractor. R.W. Rine Drlg. Co.
Issued. 1-2-43

County. Phillips



CASING:
10³/₄" 155' Cem.
7" 3692' Cem.

Elevation.

Production. Depth. Pot.
1629 BO, NoWtr

Figures Indicate Bottom of Formations.

surface, sand, shale	0-155
sand & shale	930
shale & shells	1555
red bed & shale	1720
shale & shells	2300
shale & sand	2455
shale & lime	2590
shale	2805
shale & shells	2915
shale	3135
lime	3160
shale	3187
lime	3520
cored shale (rec. 2')	3528
shale & lime	3535
cored shale (no rec.)	3541
lime & shale	3566
lime & sand	3603
shale & lime	3679
weathered granite	3692 ¹ / ₂
Total Depth.	

Tops:
Reagan 3574 (Corr.)
Granite wash. 3630
Granite 3690
Penetration 2¹/₂'

Ran Schlumberger

11-2-42: Perf. 6 shots 3570-75
200' oil in 15 min.

9 shots 3574-78
385' oil in 30 min.
900' oil in 1 hr

10 shots 3574-78
1600' oil in 1¹/₂ hrs
2100' oil in 2¹/₂ hrs
2450' oil in 3¹/₂ hrs