

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


28-5-20W

CITIES SERVICE OIL CO.
Reese "E" No. 2.

SEC.28 T.5 R.20 W
SW NE SE
990'S 990'W of E $\frac{1}{4}$ Cor.

Total Depth. 3694 Rot.TD=3691 SLM
Comm. 11-11-42 Comp. 11-21-42
Shot or Treated. None
Contractor. R.W.Rine Drig. Co.
Issued. 1-9-43

County. Phillips



CASING:

10 $\frac{3}{4}$ " 160' Cem.
7" 3691' Cem.

Elevation.

Production. Deptho.Pot.
1689 BO, No Wtr

Figures Indicate Bottom of Formations.

shale & sand	0-160
sand & shale	470
shale & shells	1280
sand & shale	1668
shale & shells	2797
shale & lime	2910
shale & shells	3112
shale & lime shells	3219
lime	3600
lime & shale	3630
lime & sand	3657
sand & shale	3686
sand hd	3691
granite hd	3694
3694 Rot.TD = 3691 SLM	
Total Depth.	

Corr. Tops:

Gorham	3556
Arbuckle	3563
Reagan	3614
Granite Wash	3653
Granite	3688
Penetration	3'

Ran Schlumberger

12-5-42 Perf. as follows:

8 shots 3597-3600

200' oil in 15 min.

400' oil in 45 min.

8 shots 3597-3600

625' oil in 1 hr.

800' oil in 1 $\frac{1}{4}$ hrs.

8 shots 3597-3600

1085' oil in 1 $\frac{1}{2}$ hrs.

1800' oil in 2 $\frac{1}{4}$ hrs.

2200' oil in 3 $\frac{1}{4}$ hrs.

2750' oil in 6 $\frac{1}{4}$ hrs.