

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


28-5-200

CITIES SERVICE OIL CO.
Reese "E" No. 3.

SEC.28 T.5 R.20 W
SW SE NE
330'N 990'W E $\frac{1}{2}$ Cor.

Total Depth. 3699=3704 SIM
Comm. 4-15-43 Comp. 4-25-43
Shot or Treated. None
Contractor. R.W.Rine Drlg.Co.
Issued. 7-10-43

County. Phillips



CASING:
8 5/8" 156' Cem.
5 1/2" 3704' Cem.

Elevation.

Production. Phy.Pot. 389 B.
No wtr

Figures Indicate Bottom of Formations.

surface & shells	0-156
shale & sand	1445
shale & shells	1667
anhydrite	1703
sdv shale & shells	1995
shale & shells	2215
shale	2347
shale & lime shells	2530
shale & shells	2665
shale & lime	2745
lime	2840
shale & lime	2975
shale & shells	3080
lime	3550
lime & sand	3565
lime	3621
lime & sand	3691
lime	3699

3699 Rot.TD = 3704 SIM
Total Depth.

Ran Schlumberger

Corr. Tops:
Arbuckle 3562
Reagan 3627
Granite Wash 3675
Granite 3703
Penetration 1

5-31-43 Perf. 12 shots 3621-23
2200' wtr in 15 min.
2400' wtr in $\frac{1}{2}$ hr
Set Lane-Wells bridge plug
at 3607 SIM. Placed 2'
rock on bridge plug

6-1-43 Perf. 34 shots 3585-91
1050' oil in $1\frac{1}{2}$ hrs
1800' oil in 4 hrs
2125' oil in 6 hrs
2700' oil in 20 hrs
 $\frac{1}{2}$ BWPH

6-4-43 Temp.Phy.Pot.
387 oil, no wtr, 24 hrs

6-7-43 Perf. 84 shots 3561-75