


28-5-20w

CITIES SERVICE OIL CO.  
Reese "E" No. 4.

SEC. 28 T. 5 R. 20 W  
SW NW SE  
990'S 330'E Center

County. Phillips

Total Depth. 3630' SIM  
Comm. 6-23-43 Comp. 7-3-43  
Shot or Treated. None  
Contractor. R.W.Rine Drlg. Co.  
Issued. 8-14-43



CASING:  
8 5/8" 153' Cem.  
5 1/2" 3630' Cem.

Elevation.

Production. Echo. Pot. 2161 B.  
No wtr

Figures Indicate Bottom of Formations .

surface	0-70
slate	158
sand & shale	565
shale & sand	1665
anhydrite	1702
shale	1850
shale & shells	2850
shale & lime	3130
lime	3632

3632 Rot. TD = 3630 SIM  
Total Depth.

Ran Schlumberger

Corr. Tops:  
Arbuckle 3539  
Reagan 3593

7-9-43 Perf. 24 shots 3575-78  
100' fluid in 1/4 hr  
200' fluid in 3/4 hr  
1400' oil in 1 1/4 hrs  
2100' oil in 1 3/4 hrs  
2675' oil in 4 1/4 hrs  
Perf. Penetration Arbuckle 39'