


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

28-5-202

Company - CITIES SERVICE OIL CO.
Farm - Reese "E" No. 9

SEC. 28 T. 5 R. 20W
NE SW SE
990' N & 990' E of S/4 Corner

County. Phillips
KANSAS



Total Depth. 3603'

Comm. 12-1-48

Comp. 12-9-48

Shot or Treated. Acid. W/1000 gals. 3569-77 12-23-48

Contractor. R. V. Kine Drlg. Co.

Issued. 2-12-49

CASING:

8-5/8" 188' Cem. W/250 Sx.

5-1/2" 3597' Cem. W/150 Sx.

Elevation. 2166' Ind.

Production. Draw-down pot. 2911
oil, no wtr. 24 hrs.

Figures Indicate Bottom of Formations.

clay & sand	90
shale	188
shale & sand	1680
anhydrite	1715
shale & shells	2960
shale & lime	3220
lime, shale & shells	3340
lime & chert	3370
lime & shale	3575
lime & sand	3603
Total Depth	

Tops:

Lansing	3305
Gorham	3555
Arbuckle	3570
Reagan	3588
Penetration	15

Perf. Pen. Reagan 4'

Drilled cement to 3595' S.L.M.

12-18-48 Perf. 21 shots 3581-88 no show

" " " Perf. 12 shots 3588-90

Fill-up 490' oil in 15 mins.

" 1150' oil in 30 mins.

" 1460' oil in 1 hour.

12-20-48 pumped 231 oil, no wtr, 11 hrs.

12-21-48 Perf. 48 shots 3569-77.

12-21-48 Perf. 12 shots 3590-92.