

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

28-5-204


Company - CITIES SERVICE OIL CO.
Farm - Reese "E" No. 10

SEC. 28 T. 5 R. 20W
NE NW SE
990' E & 330' S of Center

Total Depth. 3623' SLM
Comm. 1-19-49 Comp. 1-27-49
Shot or Treated. Acid. 1/1500 gals. 2-16-49
Contractor. R. R. Rind Drlg. Co.
Issued. 4-30-49

County. Phillips

KANSAS



Elevation. 2180 Ind.

CASING:
8-5/8" 196' Cem. 1/250 Sx.
5-1/2" 3623' Cem. 1/150 Sx.

Production. D.D. Pot. 1727 oil,
no wtr., 24 hrs.

Figures Indicate Bottom of Formations.

clay & sand	80
shale	1205
shale, shells & sand	1685
anhydrite	1725
shale & shells	2725
lime & shale	3335
lime	3615
cored, dolo. & sand	3620
cored, sand	3625
3625' RTD = 3623' SLM	
Total Depth	

Tops, Corr.:
Lansing 3323
Arbuckle 3567
Reagan 3617
Penetration 6

Drld. cem. to 3615' SLM

Perf. 90 shots 3567-3590
450' oil in 15 mins.
685' oil in 35 mins.
815' oil in 45 mins.
985' oil in 1 hour
1105' oil in 1 hr. 10 mins.
1285' oil in 1 hr. 40 mins.
2700' oil in 16 hours.