

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


28-5-20w

Company- CITIES SERVICE OIL CO.
Farm- Reese "E" No. 11

SEC. 28 T. 5 R. 20W
SW SE SE
330' N & 997' W of SEc

Total Depth. 3594
Comm. 10-12-52 Comp. 11-8-52
Shot or Treated.
Contractor. R. W. Rine Drilling Co.
Issued. 1-17-52

County Phillips
KANSAS



Elevation. 2169

Production. Pot. 131 BO 0.8%
water 24 hrs.

CASING:

8 5/8 195' w/ 200 sx cement
5 1/2 3583' w/ 150 sx cement

Figures indicate Bottom of Formations.

surface clay & sand	140
lime & shale	195
shale & shells	2435
lime & shale	3145
lime	3260
lime & shale	3378
lime	3530
cored: rec 3-3/4' shale & lime	3565
cored: rec. 4 1/2' shale & lime	3570
lime	3574
cored: rec. 4' shale & sand	3579
cored: rec. 4' sand & dolo.	3584
3584 RTD - 3583 SLM	
lime	3591
sand	3594
Total Depth	

TOPS : Corr.	
Heebner	3278
Dodge	3302
Lansing	3318
Gorham	3576
Arbuckle	3582
Reagan	3591
Penetration	3

Fillup:

330' fluid in 35 mins. at 3594'
714' fluid in 1 hr. 5 mins.
1000' fluid in 1 hr. 35 mins.
1284' fluid in 2 hrs. 5 mins.
1644' fluid in 3 hrs. 5 mins.
2064' fluid in 5 hrs. 5 mins.
2284' fluid in 7 hrs. 5 mins.
2474' fluid in 12 hrs. 5 mins.