

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

Plotted


28-5-20w

CITIES SERVICE OIL CO.
Vehige No. 3

SEC. 28 T. 5 R. 20 W.
SW NW SW
990' S 330' E of W $\frac{1}{2}$ cor.

Total Depth. 3664 $\frac{1}{2}$
Comm. 5-19-42 Comp. 6-1-42
Shot or Treated. None.
Contractor. Maboe Oil and Gas Co.
Issued. 8-8-42

County Phillips.



CASING.

85/8" 165' cemented.
5 $\frac{1}{2}$ " 3664' cemented.

Elevation.

Production. Pot. 1819 B.

Figures Indicate Bottom of Formations. 0.2% wtr Eohometer.

sand	40
sand and shells	100
shale and shells	1885
shale and lime	2732
lime and shale	3350
lime	3455
shale and lime	3530
shale and sand	3580
shale and lime	3619
cored sand (no rec)	3624
sand	3629
cored sand (no rec)	3634
sand	3644
sand and lime	3649
cored. Granite Gnoiss	
(rec 1')	3654
granite wash	3664
granite	3664 $\frac{1}{2}$

Total Depth.

Top sandy limestone	3602
Top Roagan	3613
Top Granite	3663
Penetration	1 $\frac{1}{2}$ '

June 1, 1942 Ran Schlumberger.

June 18, 1942 Porf. 12 shots 3602-3606

700' oil in 10 min.
2600' oil in 2 hours.
2800' oil in 4 hours.